

Customer Number: _____

Township: Tomahawk

SW1/4 NE1/4, E1/2 SW1/4, SE1/4 S25-34-4; NE1/4, NE1/4 NW1/4 S36-34-4; W1/2 NW1/4 S31-34-5

Bond Info: **Bond is 25% of Total Bid**

Choose method by which performance bond will be posted or secured.

Please check (✓) one: Cash or Check Irrevocable Letter of Credit

Approximate cutting area: **144** acres

Product Species		Estimated Unit Volume	Minimum Bid Per Unit	Estimated Value	Bid Per Unit	Total
20-TA	Aspen Pulp	Tons	3,500.00	10.30	36,050.00	_____
20-TMX	Mixed Hardwood Pulp	Tons	2,100.00	9.70	20,370.00	_____
20-TS	Spruce Pulp	Tons	500.00	14.00	7,000.00	_____
18-TT	Tamarack P/L	Tons	1,000.00	6.10	6,100.00	_____
10-MX	Mixed Hardwood Sawlogs	MBF	15.00	126.00	1,890.00	_____
Total estimated value of accepted bid					71,410.00	_____
Bidder's Signature _____					Date _____	Total Bid _____

Contract available for inspection

1. Clear cut area: cut all living trees greater than 1 inch in diameter except for oak, spruce, tamarack, pine, cedar, cherry, balsam fir, hemlock and yellow paint marked trees. Shelterwood harvest area: cut all ironwood and orange paint marked trees. Seed tree harvest area: cut all living trees greater than 1 inch in diameter except for pine, cedar, hemlock and yellow paint marked trees. Snags and dead trees are only to be cut if leaving them standing presents a safety hazard to the harvesting operation.
2. All logging damage/debris must be corrected/removed from trails, woods roads, and grass openings daily and prior to sale closure.
3. Any roadwork will require prior approval of the Forestry Department and will follow BMP guidelines. Contractor is responsible for installing water bars and/or using other soil stabilizing techniques where appropriate.
4. Ingress and egress to this sale is the responsibility of the contractor.
5. Contractor is responsible for obtaining permission to cross private property.
6. Special care must be taken to not damage or disturb survey markers.
7. In order to protect advanced regeneration, whole tree skidding with tops attached will be subject to field approval within the shelterwood harvest area.
8. Special care must be taken to limit damage to advanced regeneration within the shelterwood harvest area.
9. Spruce weight estimate is approximately 3% balsam fir. Mixed hardwood sawlog volume estimate is approximately 61% red maple, 20% white ash, 17% hard maple and 1% black cherry.

Variety Job

