

Customer Number: _____ Customer Name: _____

Township: **Harrison(S)**

S½ SW¼, SW¼ SE¼ S29-T34N-R8E; NW¼ NE¼, N½ NW¼ S32-T34N-R8E

Bond Info: **Bond Amount(25% of bid)\$** _____

Choose method by which performance bond will be posted or secured.

Please check (✓) one: ___ Cash or Check ___ Irrevocable Letter of Credit

Approximate cutting area: **61** acres

Product Species		Estimated Unit Volume	Minimum Bid Per Unit	Estimated Value	Bid Per Unit	Total
20-TMX	Mixed Hardwood Pulp	Tons	1,650.00	7.30	12,045.00	_____
20-TBA	Basswood Pulp	Tons	400.00	1.50	600.00	_____
20-TF	Fir Pulp	Tons	7.00	3.70	25.90	_____
20-TOR	Red Oak Pulp	Tons	65.00	3.70	240.50	_____
10-MX	Mixed Hardwood Sawlogs	MBF	7.00	111.00	777.00	_____
10-BA	Basswood Sawlogs	MBF	30.00	96.00	2,880.00	_____
10-MH	Hard Maple Sawlogs	MBF	10.00	185.00	1,850.00	_____
10-OR	Red Oak Sawlogs	MBF	3.00	225.00	675.00	_____
				Total estimated value of accepted bid	19,093.40	_____
Bidder's Signature _____					Date _____	Total Bid _____

CONTRACT AVAILABLE FOR INSPECTION

- 1) Selection harvest area: cut all ironwood, orange paint marked trees, and all trees inside of the delineated canopy gaps. Canopy gaps are delineated by purple paint marked trees located on the gap's perimeter. A purple V faces the inside of the canopy gap. Avoid damage to residual trees. Do not cut Red or Purple paint marked trees. Snags and dead trees are only to be cut if leaving them standing presents a safety hazard to the harvesting operation. Snags and dead trees cut for safety reasons must be left in the harvest area and may not be utilized.
- 2) Selection harvest area is limited to shortwood skidding only. Special care must be taken to limit damage to advanced regeneration/Special care must be taken to limit damage to saplings. All spring poles (saplings tipped over from harvesting operations) will be cut at the base.
- 3) Beaver Trail Rd - Permission must be granted by the Forestry Department to use the snowmobile trail from December 1 to March 31. Ample snow cover must be maintained to allow safe snowmobile operation.
- 4) Do not operate equipment within 15 feet of the Ordinary High Water Mark (OHWM), ephemeral ponds, and wetlands unless the ground is firm or frozen. Do not operate equipment within 15 feet of lakes.
- 5) Garlic Mustard has been found on the snowmobile trail and woods road system (See map). To help prevent the spread of garlic mustard, ground disturbance must be kept to a minimum.
- 6) All logging damage/debris must be corrected/removed from trails, woods roads, and grass openings daily and prior to sale closure. Slash will be left where it falls unless the contractor wishes to use it to prevent ruts, soil compaction and erosion during logging operations.
- 7) Any roadwork will require prior approval from the Lincoln County Forestry Department and must follow BMP guidelines. Contractor is responsible for installing broad based dips, water bars and/or using other soil stabilizing techniques where appropriate.
- 8) Gates/Berms removed or damaged by the contractor must be restored to original or better condition when the sale becomes inactive and upon sale completion.
- 9) Ingress and egress to this sale is the responsibility of the contractor.
- 10) Mixed hardwood sawlog volume estimate is approximately: 90% white ash and 8% red maple.

Hamrer Hippyer

