

Customer Number: _____ Customer Name: _____

Township: **Harrison(S)**

E½ NW¼ S29-T34N-R8E; NW¼ SE¼ S31-T34N-R8E

Bond Info: **Bond Amount(25% of bid)\$** _____

Choose method by which performance bond will be posted or secured.

Please check (✓) one: Cash or Check Irrevocable Letter of Credit

Approximate cutting area: **12 acres**

Product Species		Estimated Unit Volume	Minimum Bid Per Unit	Estimated Value	Bid Per Unit	Total
18-TPR Red Pine P/L	Tons	1,450.00	23.50	34,075.00	_____	_____
20-TMX Mixed Hardwood Pulp	Tons	3.00	6.50	19.50	_____	_____
Total estimated value of accepted bid				34,094.50	_____	_____
Bidder's Signature _____					Date _____	Total Bid

CONTRACT AVAILABLE FOR INSPECTION

- 1) Clearcut area: Cut all Trees. Tops from the Pine clear cut area must be cut into lengths no longer than 5 ft; tops and slash CANNOT be wind-rowed but must be evenly distributed across the site. Slash will be left where it falls unless the contractor wishes to use it to prevent ruts, soil compaction and erosion during logging operations. All Snags: must be cut down to 8" dia. Small end and decked roadside; the remainder of the Snag will be cut into lengths no longer than 5 ft. **No equipment may operate within 15' of the OHWM of Kordick Lake.**
- 2) All logging damage/debris must be corrected/removed from trails, woods roads, and grass openings daily and prior to sale closure.
- 3) Any roadwork will require prior approval from the Lincoln County Forestry Department and must follow BMP guidelines. Contractor is responsible for installing broad based dips, water bars and/or using other soil stabilizing techniques where appropriate.
- 4) Ingress and egress to this sale is the responsibility of the contractor.
- 5) All stump heights must be less than 6"
- 6) This sale is a red pine harvest and Lincoln County's HRD (Heterobasidion root disease) Policy must be followed during the harvest.
- 7) Pulp weight estimates include all saw logs.

Lochaber

