

Township: **Birch**

Customer Number: \_\_\_\_\_

**N<sup>1</sup>/<sub>2</sub> NE<sup>1</sup>/<sub>4</sub>, SW<sup>1</sup>/<sub>4</sub> NE<sup>1</sup>/<sub>4</sub>, NW<sup>1</sup>/<sub>4</sub> SE<sup>1</sup>/<sub>4</sub> S1-T33N-R7E**

Bond Info: **Bond is 25% of Total Bid.**

Choose method by which performance bond will be posted or secured.

Please check (✓) one:  Cash or Check  Irrevocable Letter of Credit

Approximate cutting area: **74 acres**

Product Species	Estimated Unit Volume	Minimum Bid Per Unit	Estimated Value	Bid Per Unit	Total
20-TA Aspen Pulp	Tons 370.00	7.60	2,812.00	_____	_____
20-TMX Mixed Hardwood Pulp	Tons 900.00	6.80	6,120.00	_____	_____
20-TBA Basswood Pulp	Tons 120.00	1.40	168.00	_____	_____
20-TOR Red Oak Pulp	Tons 1,150.00	3.40	3,910.00	_____	_____
10-MX Mixed Hardwood Sawlogs	MBF 15.00	126.00	1,890.00	_____	_____
10-BA Basswood Sawlogs	MBF 2.00	109.00	218.00	_____	_____
10-OR Red Oak Sawlogs	MBF 50.00	252.00	12,600.00	_____	_____
Total estimated value of accepted bid			<b>27,718.00</b>	_____	_____
Bidder's Signature _____				Date _____	<b>Total Bid</b>

**Contract Available for Inspection**

- 1) Clear cut area: cut all living trees >1 inch in diameter except for oak, butternut, spruce, pine, cherry, hemlock and balsam fir. Do not cut non-merchantable trees in low wet areas/drainages. Selection harvest area: cut all ironwood, orange paint marked trees, all purple paint marked trees and all trees inside of the delineated canopy gaps. Canopy gaps are delineated by purple paint marked trees along the gap's perimeter. A purple V faces the inside of the canopy gap. Snags and dead trees are only to be cut if leaving them standing presents a safety hazard to the harvesting operation.
  - 2) All logging damage/debris must be corrected/removed from trails, woods roads, and grass openings daily and prior to sale closure.
  - 3) Any roadwork will require prior approval from the Lincoln County Forestry Dept. and will follow BMP guidelines. Contractor is responsible for installing water bars and/or using other soil stabilizing techniques where appropriate.
  - 4) Ingress and egress to this sale is the responsibility of the contractor.
  - 5) Gates/Berms removed/damaged by the contractor must be restored to original or better condition when the sale becomes inactive and upon sale completion.
  - 6) Special care must be taken to not damage or disturb survey markers.
  - 7) In order to protect advanced regeneration whole tree skidding with tops attached will be will be subject to field approval.
  - 8) Special care must be taken to limit damage to advanced regeneration.
  - 9) Logging activity will be prohibited from April 15 to July 15 of each year to reduce the risk of introducing and/or spreading oak wilt.
  - 10) Mixed hardwood pulp estimate is approx.: 5% white birch. Mixed hardwood sawlog volume estimate is approx.: 99% white ash. Northern red oak sawlog volume is approx.: 2% hard maple.
  - 11) Garlic mustard has been found on several woods roads within and adjacent to the sale (see map). Soil disturbances on these woods roads must be kept to a minimum. The road must have ample snow cover to limit the spread of Garlic Mustard seed. This sale must be cut during frozen, snow covered conditions.
  - 12) Permission must be granted by the Forestry Dept. to use the snowmobile trail from December 1 to March 31. Ample snow cover must be maintained to allow safe snowmobile operation.
  - 13) Contractor is responsible for obtaining permission to cross private property.
- Vespillone Job

